

610 MUNI **CONSTRUCTION SPECIFICATION FOR THE REMOVAL OF ELECTRICAL
EQUIPMENT AND MATERIALS**

610.07.04 **Demolition**

Add in the following to the second paragraph:

The broken edges of the structure to remain in place shall be saw cut to their full depth to expose a fresh, straight, vertical surface along the squares up limits of the proposed excavation.

610.07.09.02 **Packaging of Electrical Equipment and Materials**

Delete the last paragraph:

Add in the following:

Where temporary storage of equipment is required, materials other than traffic signal controllers and electronic components shall be stored in accordance with the contract documents.

610-01