

## Basis of Payment Summary of Revisions

Standards Committee Annual Review

March 2024

REMOVED/ADDED/REVISED	
<b>Operational Constraints</b>	Revised Traffic Requirements Protection and Repair of Property, Structures and Utilities – revised to include new directions to Enbridge third party requirements
<b>Restoration</b>	Renamed Other Landscaping Features to Reinstatement of Existing Landscaping Features and revised the scope.
<b>Seasonal Shutdown</b>	Created new standard SP based on items from previous contracts
<b>180 – Management of Excess Materials</b>	New Standard SP for the disposal of non-reusable materials
<b>206 – Earth Excavation and Grading</b>	New reference to OPSS 120 for rock excavation outside of trenches
<b>310 – Hot Mix Asphalt</b>	Revisions to length of placement Revised summary of asphalt tonnage Revised minimum repair length to 50m Designer Consideration for surface smoothness revised to include what MTO SP to review for exemptions
<b>311 – Asphalt Sidewalk, Driveway, Boulevard and Sidewalk Resurfacing</b>	Title revised to match OPSS
<b>314 – Untreated Granular Subbase, Base, Surface, Shoulder and Stockpiling</b>	Title revised to match OPSS New reference to OPSS 102 Weighing of Materials Revised to include timing and weather restrictions on the placement of RAP Added designer consideration to confirm road width and thickness for placed RAP Removed depots as a default location to deliver unused RAP materials
<b>355 – Installation of Interlocking Concrete Pavers</b>	Title revised to match OPSS
<b>403 – Rock Excavation for Pipelines, Utilities and Associated Structures</b>	New Standard SP carried forward from 2023 contracts
<b>405 – Pipe Subdrain</b>	Title revised to match OPSS
<b>441 – Watermain Installation in Open Cut</b>	Revised to included new PVC material specification when Nitrile gaskets are to be specified in the contract. Revised to include new construction specification for service connections from property line to exterior foundation wall
<b>703 – Permanent Small Signs and Support Systems</b>	New standard SP carried forward from previous years contracts
<b>802 - Topsoil, Imported</b>	New standard SP changing the measurement of payment from cubic meters to square meters at a depth of 100 mm. carried forward from 2023 contracts
<b>805 – Temporary Erosion and Sediment Control</b>	Added reference to CSA W208:20 Revised schedule for the submission of the records of inspection Revised the schedule for payment