

March 25, 2022

Walter Street, Coniston

Walter Street Bridge Replacement

The City of Greater Sudbury will be completing a **Bridge Replacement on Walter Street, Coniston, between 32 and 34 Walter Street.**

Construction Details:

- Removal of the existing Walter Street Bridge including guiderail, abutment, retaining walls, wing walls and foundation.
- Remove and replace existing asphalt pavement and waterproofing
- Supply and install new open-bottom precast concrete culvert
- Supply and form new concrete distribution slab
- Install new reinforced concrete sidewalk and transition ramp
- Supply and form new gabion basket walls
- Place substrate in creek bed backfill, compact and grade road surface
- Reconstruction of the road approaches
- Remove and replace existing watermain per limit

Expected Start Date: Spring 2022


Expected End Date: Fall 2022

The construction phase of the Project is anticipated to be carried out between **May** and **November 2022.**

Timeline is subject to change



For more information, please visit www.greatersudbury.ca/2022construction. If you do not have access to the website, please contact the Project Team members listed below and a package with further project details can be mailed to you.

	<div>Before Construction Begins:</div> <ul style="list-style-type: none">• Work crews will mark the locations of underground utilities, such as gas, water and cable so that the construction work does not interfere with these utilities.• Once a Contractor has been selected, affected property owners will receive a construction notice with more information about the work.• The City is not responsible for damage to any privately-owned items on the municipal right-of-way. Property owners should remove items located within the municipal right-of-way, such as landscaping, fencing, sprinkler systems and decorative objects.• Once Walter Street has been repaved with new asphalt, roadway cuts to install new utilities will not be permitted for a period of three years. Therefore, you should contact your hydro, gas, telephone or cable providers should you require changes to these services as well as notify the Project Manager below.• Should you wish to make any modifications to your property entrance, please contact the Project Manager listed below prior to April 4th.• Pile driving is required as part of the construction, you will be contacted regarding a pre-construction survey of your home to be completed prior to pile driving operations commencing.• The pre-construction and post construction surveys are conducted by a third-party consultant and is a visual inspection of your home and other structures complete with photos and / or videos of specific locations of concerns. The consultant will be required to enter the home to complete the interior portion of the survey. The consultant will respect the privacy of all homeowners and will not utilize photos that are in concern of homeowners.
---	---

Questions about upcoming construction can be directed to:

Project Manager:
Chris Cornell, P.Eng.
705-674-4455, extension 4239
705-688-6734 (cell)
chris.cornell@greatersudbury.ca

Project Designer:
Mike Neumann, P.Eng.
(905) 361-6534
mneumann@planmac.com