492 MUNI CONSTRUCTION SPECIFICATION FOR SITE RESTORATION FOLLOWING INSTALLATION OF PIPELINES, UTILITIES AND ASSOCIATED STRUCTURES

ADD in the following subsection:

492.07.10 Driveway Restoration

Reconstruction of existing paved driveways shall be a minimum150 mm Granular ‘A’, and a minimum 50 mm asphalt surface course, or existing depth, whichever is greater.

Reconstruction of existing gravel driveways shall be a minimum 150 mm Granular ‘A’, or existing depth, whichever is greater.

Reconstruction of existing lockstone driveways shall be a minimum 50 mm Crusher dust material, and 150 mm Granular ‘A’, or existing depth, whichever is greater.

Existing slag driveways, material shall be salvaged, stockpiled on site and re-used.

492.07.11 Utility Restoration

Underground utilities impacted by the work shall be restored to the requirements specified by the appropriate utility.