

**610 MUNI                      CONSTRUCTION SPECIFICATION FOR THE REMOVAL OF ELECTRICAL  
EQUIPMENT AND MATERIALS**

**610.07.04                      Demolition**

**ADD in the following to the second paragraph:**

The broken edges of the structure to remain in place shall be saw cut to their full depth to expose a fresh, straight, vertical surface along the squares up limits of the proposed excavation.

**610.07.09.02                      Packaging of Electrical Equipment and Materials**

**DELETE the last paragraph.**

**ADD in the following:**

Where temporary storage of equipment is required, materials other than traffic signal controllers and electronic components shall be stored in accordance with the contract documents.