

620 MUNI **CONSTRUCTION SPECIFICATION FOR TRAFFIC SIGNAL EQUIPMENT
AND ELECTRICAL TRAFFIC CONTROL DEVICES**

620.05.08 **Junction Boxes and Fittings**

ADD in the following:

Fibreglass reinforced concrete junction boxes for curbside loop detector and lead-in connections shall be "Quazite" with the label "TRAFFIC" impressed into the cover, or as indicated in the contract.

620.07.02.04 **Signal Heads**

Delete second and third paragraphs:

ADD in the following:

Opaque jute sacking or plastic film shall entirely cover the signal heads and remain securely in place until all tests have been completed and the signal heads have been put into operation. Pedestrian signal heads shall be turned to face the pole prior to operation.

Signal heads shall be adjusted for maximum visibility and focussing prior to final tightening of hardware. Unused hubs in signal heads shall be plugged with sealing caps, without gaskets.